



## Surveillance Report

March 04, 2020

I.C.T. company is honored to provide the Indian Embassy in Damascus with the following technical report for the building, installing, and painting of the gate of the Embassy in Damascus

### 1. Introduction

The Indian Embassy in Damascus is planning on rehabilitating the gate of the Embassy and tare down the cracked wall around the gate and rebuild it into an arch shape entrance to improve the safety and security of the Embassy and reflect a more modern and civilized exterior.

### 2. Materials

Gate:

The total area is approximately 13.5 square meters

The space is approximately 5.5 square meters

The front work area is approximately 8 square meters


The total work area is approximately 19 square meters  
(front and back and sides)

The marble or the natural stone needed to cover the area is approximately 20 square meters.

The building blocks needed for the wall is approximately 100 building blocks

The Cement needed is approximately 15 bags of 50 kgs

The needed iron is approximately 600-800 kgs



I.C.T.